



## American Samoa Power Authority

---

P.O. Box PPB

Pago Pago, American Samoa 96799

Telephone: (684) 699-1234/248-1234

Email: [info@aspower.com](mailto:info@aspower.com) & Website: [www.aspower.com](http://www.aspower.com)



ISSUANCE DATE: **September 11, 2018**

RFP NO.: **RFP No. 18.040.ESD-WTR IN-LINE METERS (RE-BID)**

SUBJECT: **Addendum No. 1**

The American Samoa Power Authority hereby issues Addendum No. 1 to amend Request for Proposals (RFP) requirements. This addendum is issued pursuant to the conditions of the RFP documents and is hereby made part of the RFP. The addendum serves to clarify, revise, and supersede information contained in the RFP. The Offeror must acknowledge receipt of this addendum in the appropriate space provided in the Addendum Form. Failure to do so may subject the Offeror to disqualification.

This Addendum No. 1 to the Request for Proposals (RFP) for RFP No. 18.040.ESD-WTR – IN-LINE METERS (RE-BID) issued by American Samoa Power Authority to respond to questions received from potential Offerors submitted by September 30<sup>th</sup>, 2018 deadline. This Addendum No. 1 is hereby incorporated into the RFP.

### QUESTIONS RECEIVED FROM POTENTIAL OFFERORS:

1. **Q-1:** Are the main lines under the asphalt or concrete roadway?  
**A-1:** Waterlines at sites #9B and #3 are under side of the road, the other three are not.
2. **Q-2:** Drawings for Malaeimi Vault Extension.  
**A-2:** As discussed during the Pre-proposal meeting, ASPA provided a guideline (SOW). The contractor is required to provide their Technical Proposal (SOW) i.e. their Approach and methodology. This is one of the three Criterias for evaluation/ selection.
3. **Q-3:** Pressure Test – does the flow meter installed during the test?  
**A-3:** All pipes & fittings & joints shall be tested.
4. **Q-4:** Vault Aluminum Cover. Please specify if locally yard fabricated or manufacturers pre-fab item. If Pre-fab please specify.  
**A-4:** The specifications for the material is provided. The contractor has the option of Purchase locally or from off island, pre fab or not.
5. **Q-5:** What is the flow meter length?  
**A-5:** 6" meter = 27, 8" meter = 30 – 1/8", 10" meter = 41-1/8"

Should you have any questions or need clarification, please call me at 248-1234.

Sincerely,

 2018 September 11

**Ioana S. Uli**  
Procurement Manager

Please sign and date below to acknowledge receiving Addendum 1. You may return this document via email to the ASPA Procurement Office at [bids@aspower.com](mailto:bids@aspower.com).

---

**ACKNOWLEDGEMENT OF RECEIVING ADDENDUM 1**

Received by \_\_\_\_\_, this \_\_\_\_\_ day of August, 2018.  
Company \_\_\_\_\_ Title \_\_\_\_\_  
Fax No. \_\_\_\_\_ Email Address \_\_\_\_\_